



# TOB Report

*Slawek Tkaczyk*  
*Fermilab*  
*CMS Week*

*Thanks to Lenny, Kenan, Tim, Wim for information and many slides*




# Module Production

•US production lines underwent upgrades to significantly increase production capacity to recover lost schedule time.

- New and better methods
- More and better tooling and hardware
- Better software and Quality Control

•Both FNAL and UCSB production lines have demonstrated stable, high quality module production at high rates

•15 modules/day/site






# Module Testing

- The testing cycle ~12 hr
  - In order to maintain 15 module per day rate of production
  - 10 modules/test session
  - Includes readout at
    - +23 °C, -20 °C, +20 °C, -20 °C, and +20 °C.
  - LT\_1\_24 used;
  - results tend to agree with ARC fast test results
    - Module grades are based on ARC testing
- System ran reliably throughout the high-rate exercise



LT system









# Testing Results - LT

- Some modules showed high noise at  $-20\text{ }^{\circ}\text{C}$  in the PeakInvOn mode.
- Traced to cases with 8 or more modules in the Vienna box. Re-testing, with fewer than 8 modules, showed that the noise is an artifact of the testing arrangement.

**In general there is good agreement between the ARC and LT test results and we do not see (real) problems at low temperature.**





# Module Testing




**Gantry makes modules**




**Wire bond**




**Module quick test**



**Storage/Mount on Rods**



**Pinhole tests**



**Thermal cycle modules  
2 loads, 8 hours each**






# Summary of Tests

- Production Rate of 15 modules/day demonstrated.
  - techniques, procedures, and equipment were refined.
- 302 modules were produced and fully tested in US
- Quality of the modules is high.
  - Problems should drop with new hybrids, new ST, & HPK sensors
- Testing infrastructure is ready for the large scale module production
- Testing facilities have trained personnel and with sufficient experience



# ROD Structures

- Major components are Command and Control Unit (CCU), and Analog Opto-hybrids (AOH).
- CCU handles communication between rods, and between rod and readout electronics.
- AOH converts module's electrical output to optical signal.
- Both of these components, as well as electrical connectivity of the whole, are tested at CERN prior to shipping.
- Carbon-fiber frame produced in Helsinki, and assembly of CCU's AOH's and support electronics at CERN.





# Rod Testing

- Plan is to perform burn-in once rods are assembled
  - Use of commercial chest freezers and chillers for the burn-in facility
  - Thermal-cycling tests to be done during burn-in specified.
- Rods are cycled over 72 hours
  - 15 modules/day  $\Rightarrow$  12.5 (SS) rods/week
  - 2 1/3 cycles/week  $\Rightarrow$  5-6 rods/cycle
- As with the ARC and LT systems we expect that much of the loading, initializing, and monitoring will be carried out by technicians.
- The single rod and multi-rod readout systems are commissioned at FNAL and UCSB, but these are very similar to the LT system (CMS DAQ components).
- **Basic functionality achieved.**



**The multi-rod burn-in thermal controls and interlocks are working well ahead of schedule at both production sites.**



# Rod Testing

- **Single rod test stand commissioned**
  - Rod to fiber optic cable to OEC to F-MUX with 4 cards to 4 FED channels
  - HV/LV operational
  - FEC to FECtoCCUM patch card to FECtoCCUM card to CTRL IN and CTRL OUT on ROD
- **Configured LtStruct to readout single rod**
  - Fiber optic channels mapped to F-MUX channels
  - Timing adjustments to FED to get it to readout after F-MUX switch



# Multi Rod Test Stand

- **DAQ System setup**
  - FEC connected to FECtoCCUM card.
    - Two types of FEC's with different interconnections
  - Need one more TPO to make Rod Test systems identical
  - Software LtStruct used for both
  - Multi-rod configuration files checked out
  - Mapped additional (6) optical fibers to other F-MUX channels



# Power Supplies

- All power supplies have arrived from CERN
  - 8 rod power supplies, cables and tails
    - 2 tails had short circuits
  - 1 power supply with cable to power CCU ring through FECtoCCUM board
- All power supplies are mounted in the rack and integrated with the interlock
- HV channels added using patch cables



# LT Rod Test Stand



8 Rods assembled and being readout



# Conclusions

- Module LT Test Stand handling up to 10 modules.
- Single and Multi- Rod Test Stands commissioned.
- 6 rods readout at FNAL (and UCSB) in the rod burn-in stand
- The Test Beam results show good performance of components.



# LT SW Status - June 2004 (Wim)

- Two versions available:
  - LT\_1\_24 (in 3 flavors: TIB,TOB,TEC)
  - LT\_2\_0 (beta version; 1 flavor fits ALL!)
- Status of LT\_1\_24 release:
  - TSC driver modified to increase reliability for 10-module operation.(I2C commands scrambled)
- Status of LT\_2\_00 pre-release:
  - Many changes (new TSC driver, DCU integrated w/ DB,...)
  - More convenient AFS distribution
- Status of LSubstructure\_0\_13 release:
  - Basic functionality implemented: time and opto tunings, multiple structures (6 run tested!), integrated with slow controls.